

**GENERAL NOTES**

1. ALL DIMENSIONS AND EXISTING CONDITIONS ARE TO BE FIELD VERIFIED BEFORE BEGINNING CONSTRUCTION. DO NOT SCALE DRAWINGS.
2. DIMENSIONS ARE TAKEN FINISHED FACE OF PARTITION TO FINISHED FACE OF PARTITION.
3. ALL INTERIOR MATERIALS & FINISHES TO BE BUILDING STANDARD, TENANT APPROVED, INCLUDING BUT NOT LIMITED TO WALL/FLOOR/CEILING MATERIALS/FINISHES AND WINDOW COVERINGS.
4. ALL ELECTRICAL AND DATA SYSTEMS/WIRING/FIXTURES TO BE BUILDING STANDARD.
5. ALL MECHANICAL SYSTEMS AND FIXTURES TO BE BUILDING STANDARD. MECHANICAL SYSTEM SHALL BE BALANCED.
6. ALL NEW DOORS TO BE 3'-0" WIDE WITH ADA APPROVED HARDWARE, BUILDING STANDARD, OWNER APPROVED,
7. ALL LEVERS/HARDWARE FOR DOORS WITHIN THE AFFECTED AREA BY ALTERATION SHALL BE ADA COMPLIANT, BUILDING STANDARD, TENANT APPROVED, INCLUDING DOORS LEADING TO THE AFFECTED AREA ALONG THE ACCESSIBLE ROUTE.

**GRAPHIC SYMBOLS**


- ===== NEW PARTITION
- EXISTING PARTITION
- - - - - DEMOLISHED PARTITION
- ⊗ NEW EXIT LIGHT
- ⊙ E.T.R. EXIT LIGHT-EXISTING TO REMAIN

**CODE DATA**

OCCUPANCY: BUSINESS  
 CONSTRUCTION TYPE: 3B  
 STORIES: 2  
 SPRINKLED: YES  
 AFFECTED FOOTPRINT AREAS: 1,093 +/- SQUARE FEET




**DIMENSION IV  
MADISON**

Architecture  
 Engineering  
 Interior Design  
 313 West Bellline Hwy., Suite 161  
 Madison, WI 53713  
 phone (608) 229-4444 fax (608) 229-4446




**ABR EMPLOYMENT SERVICES**


TOWN CENTER SQUARE  
 6802 ODANA ROAD  
 MADISON, WISCONSIN 53719



**1 PARTIAL SITE PLAN - ACCESSIBLE ROUTE**



**2 PARTIAL SECOND FLOOR PLAN**



**2 PARTIAL SECOND FLOOR PLAN**



DATE OF ISSUE:	12.30.04
REVISIONS:	
PROJECT #:	04101

PARTIAL SITE PLAN,  
 FLOOR PLAN &  
 NOTES.

**A1.1**